



### CONTRACTOR'S RESPONSIBILITY

Erosion and Sedimentation controls are performance based criteria. If the BMPs provided do not prevent soils from leaving a construction site, then the Contractor is required to employ additional procedures to provide clean runoff from a site.


#### STEP 1. Set stakes





#### STEP 3. Staple filter material to stakes and extend it into the trench



#### STEP 2. Excavate a 4" x 4" trench upscale along the line of stakes



#### STEP 4. Backfill and compact the excavated soil



5/18/15	CONTRACTOR NOTE ADDED	S.R.
DATE	REVISION DESCRIPTION	APP

CITY OF CLEARWATER  
ENGINEERING DEPARTMENT  
EROSION AND SILTATION  
CONTROL POLICY

INSTALLING A  
FILTER FABRIC SILT FENCE

INDEX NO.	PAGE NO.
607	2 OF 3
LATEST REVISION	2/22/2016