

CONTRACTOR'S RESPONSIBILITY


Erosion and Sedimentation controls are performance based criteria. If the BMPs provided do not prevent soils from leaving a construction site, then the Contractor is required to employ additional procedures to provide clean runoff from a site.



STANDARD DETAIL TRENCH WITH NATIVE BACKFILL



ALTERNATE DETAIL
TRENCH WITH GRAVEL



N.T.S.

NOTES:

- Inspect and repair fence after each storm event and remove sediment when necessary.
- Removed sediment shall be deposited to an area that will not contribute sediment off—site and can be permanently stabilized.
- 3. Silt fence shall be placed on slope contours to maximize ponding efficiency.

5/18/15	CONTRACTOR NOTE ADDED	S.R.
DATE	REVISION DESCRIPTION	APP

CITY OF CLEARWATER
ENGINEERING DEPARTMENT
EROSION AND SILTATION
CONTROL POLICY

INSTALLING A FILTER FABRIC SILT FENCE

INDEX NO.	PAGE NO.
607	3 of 3
LATEST	2/22/2016